



JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION

**Jharkhand State Cooperative Milk Producers' Federation Ltd**

Near Farmers Training Centre Campus, Sec-II, H.E.C., Dhurwa,  
Ranchi – 834004, Jharkhand

Phone no: 7544003404/7360035219/0651-2443055/62

Email: [purchase@jmf.coop](mailto:purchase@jmf.coop)

WEBSITE: [www.jmf.coop](http://www.jmf.coop)

**TENDER DOCUMENT**

**FOR CONSTRUCTION OF PRODUCT PACKING ROOM & COLD  
STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT,  
HOTWAR**

**TENDER NO. JMF-PP-Construction of P-P Room/2020-21/071**



Date of Publish of Tender : 11 Jan 2021

Last date for submission of Sealed Tender : 28 Jan 2021 by 5:00 PM

Name of Tenderer: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Telephone no: \_\_\_\_\_

Email Id \_\_\_\_\_

**Tender Fee: Rs. Nil/-**

All rights reserved. This material is confidential and proprietary of The Jharkhand State Co-operative Milk Producers' Federation Ltd (JMF) and no part of this material should be reproduced, published in any form by any means, electronic or mechanical including photocopy or any information storage or retrieval system nor should the material be disclosed to third parties without the written authorization of JMF



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

TENDER NO. JMF-PP-Construction of P-P Room/2020-21/071

**BIDDING DOCUMENT  
FOR CONSTRUCTION OF PRODUCT PACKING ROOM & COLD  
STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT, HOTWAR  
(COMPLETE BIDDING DOCUMENT)**

**Time schedule for tender process:**

|   |  |
|---|--|
| Date of publication of tender                   | 11 Jan 2021  |
| Distribution of tender document commence from   | 11 Jan 2021  |
| Last date for distribution of tender document   | 27 Jan 2021  |
| Last date for receipt of duly filled in tenders | 28 Jan 2021 by 5:00PM                                      |
| Opening of Technical Tender:                    | 30 Jan 2021 @ 12:30PM                                      |
| Opening of Financial Tender:                    | Shall be notified Later after opening of<br>Technical Bid. |

**Note: This tender document contains 24 pages (total no. of pages including Annexure) and tenderers are requested to sign on all the pages.**



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**INDEX**

| <b>S. No</b> | <b>Particulars</b>  | <b>Page No.</b> |
|--------------|---|-----------------|
| 1.           | Introduction  | 4               |
| 2.           | Notice Inviting Tender  | 5               |
| 3.           | Instruction to Bidder   | 7               |
| 4.           | Eligibility and Qualification Requirements                                  | 8               |
| 5.           | Earnest Money Deposit   | 9               |
| 6.           | Scope of Work   | 10              |
| 7.           | General Terms and Conditions  | 11              |
| 8.           | Vendor Registration Form  | 13              |
| 9.           | Performa of Technical Bid   | 14              |
| 10.          | Performa of Financial Bid   | 15              |
| 11.          | Detailed BOQ/SOQ of Product Packing & Cold Storage<br>Platform Construction | 20              |
| 12.          | Performa of Undertaking & Acceptance Letter                                 | 23              |
| 13.          | Certificate Of No Deviation   |                 |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

## **1. INTRODUCTION:**

When the famous White Revolution of the seventies and eighties – Operation Flood - swept through the country, Jharkhand, then a part of undivided Bihar served merely as a market and saw little of its benefits. Even though India stood self-sufficient in milk production, the eastern state of Jharkhand still depends on import of milk from other states. It was only in June 2013 when **Jharkhand State Cooperative Milk Producers' Federation Ltd. (JMF)** registered office at H.E.C., Sec-II, Dhurwa, Ranchi, (Jharkhand) – 834004 was formed by the Government of Jharkhand under Jharkhand Co-operative Societies Act, 1935 with brand name '**Medha**' with an aim to promote dairying as a source of livelihood in the rural parts of the state and propel Jharkhand towards self-reliance in milk and milk products.

**JMF** under the management of National Dairy Development Board (NDDB) started the milk procurement, processing and marketing activities in the state after taking over the existing Government Dairy at Ormanjhi in August 2014 and subsequently three other dairies at Deoghar, Koderma & Latehar. In 2016 NDDB supported in building a 1 Lakh Litre State of the Art Dairy Plant at Hotwar, Ranchi for the Jharkhand Milk Federation and today it is providing an alternative livelihood options to around 20000 rural families in the state of Jharkhand.

Jharkhand (झारखण्ड) is a state in eastern India. Ranchi was the centre of the Jharkhand movement (a movement called for a separate state for the tribal regions of South Bihar, northern Orissa, western West Bengal and the eastern area of what is present-day Chhattisgarh). The Jharkhand state was formed on 15 November 2000 by carving out the Bihar divisions of Chota Nagpur and Santhal Parganas. It's known for its waterfalls, the elegant Jain temples of Parasnath Hill and the elephants and tigers of Betla National Park.

Ranchi, the state capital has been selected as one of the hundred Indian cities to be developed as a smart city under PM Narendra Modi's flagship Smart Cities Mission. The city has a moderate climate and was the summer capital of Bihar until Jharkhand was separated in the year 2000. It is popularly known as a "City of Water Falls".

Area: 652 km<sup>2</sup>

Metropolitan area: 1,295 km<sup>2</sup>

Elevation: 651 m

Weather: 34 °C, Wind N at 13 km/h, 29% Humidity

Population: 10.7 lakhs (2011)

The word '**Medha**'  means Goddess Sarasvati-the Deity of Knowledge. Like the purity of the reverent deity, our sincere effort is to provide the people of Jharkhand the best of nature.

*Our core philosophy at Medha is to stay true to our roots with a commitment to serve the people of the state with the best quality, hygienic, unadulterated milk which contributes to the development of a healthy and strong people i.e.,*

**'Har boond mein Sehat, Har boond mein Jharkhand'**



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

## **2. NOTICE INVITING TENDER:**

The Jharkhand State Cooperative Milk Producers' Federation Ltd ("PURCHASER"), Ranchi invites sealed tenders under "**TWO BID SYSTEM**" for selection of an expert agency for the purpose of Civil Construction of Product Packing Room & Cold Storage Platform Work at the "JSCMPFL" (Jharkhand State Cooperative Milk Producers' Federation Ltd).

The details of the tender are given as below:

- 1) **Tender Notice Number:** JMF-PP-Construction of P-P Room/2020-21/071
- 2) **Name of Work:** Civil Construction of Product Packing Room & Cold Storage Platform Work at Medha Dairy Plant, Hotwar
- 3) **Completion Time:** 90 days from the date of issue of order/contract.
- 4) **Estimated Cost:** Not applicable
- 5) **Tender Document Cost:** Nil
- 6) **Earnest Money Deposit:** Rs 26,000/-
- 7) **Last Date & Time for receipt of Completed Tender.:** Before 5.00 P.M. on 28.01.2021.
- 8) **Date & Time of tender Opening: Technical bid:** At 12.30PM on 30.01.2021.
- 9) **Place of submission of Tender:** Medha Dairy Plant, Beside Birsa Munda Central Jail, Hotwar, Ranchi-835217, Jharkhand
- 10) **Period of Contract / Completion of Job:** 3 months (90 Days) from the date of order/contract.

Note: The tenderer shall return the duly filled in tender document after affixing signature on all the pages of the Tender Documents.

Correspondence Address:

JHARKHAND STATE COOPERATIVE MILK PRODUCERS' FEDERATION LTD, FARMERS TRAINING CENTRE, HEC, SEC- 2, DHURWA, RANCHI – 834004

"**TWO BIDS SYSTEM**" shall be followed for this tender. Tenderer should take due care to submit the tender in accordance with requirement in sealed covers. Bids received shall be evaluated as per the Criteria prescribed in the tender document. Jharkhand State Cooperative Milk Producers' Federation Ltd ("PURCHASER") will not entertain any modifications subsequent to opening of bids and bids not conforming to tender conditions shall be liable to be rejected. Therefore, bidders are advised to submit their bids complete in all respects as per requirement of tender document specifying there.

Acceptance to all the clauses of Bid Evaluation Criteria, General terms and conditions and compliance to the Scope of Work requirement etc.

Tender documents for Civil Construction of Product Packing Room & Cold Storage Platform Work at Medha Dairy Plant, Hotwar can be obtained from office of the Purchase Officer from **11 Jan 2021 to 27 Jan 2021** on all working days between **11 A.M. to 4 P.M.**

The tender document can also be downloaded from the JMF's official website [www.jmf.coop](http://www.jmf.coop)



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**EVALUATION OF TENDERS**

- 1.1 The JMF shall evaluate the bids in respect to the substantive responsiveness of the bid or otherwise.
- 1.2 The JMF shall carry out detailed evaluation of the substantially responsive bids. The Purchaser shall check the bid to determine whether they are complete, whether any computational errors have been made or required sureties have been furnished.
- 1.2 Arithmetical error shall be rectified on the following basis: -
- a) If there is a discrepancy between the unit price and total price that is obtained multiplying the unit price and quantity, the unit price shall prevail and the total price shall be corrected by the JMF.
  - b) In case of discrepancy between words and figures, the amount in words shall prevail.

The EMD draft should be kept in the Technical Bid Cover. The Technical bid and the financial bid should be sealed by the tenderer in separate covers duly super scribed as “Technical Bid” and “Financial Bid” respectively. Both these sealed covers should then be kept in a bigger cover which should also be sealed & duly super scribed as **“TENDER FOR CIVIL CONSTRUCTION OF PRODUCT PACKING ROOM & COLD STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT, HOTWAR, RANCHI”**.

Managing Director  
Jharkhand State Cooperative Milk  
Producers' Federation Ltd



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**Instruction to Bidder / Tenderer**

1. The Bidder is expected to examine all instructions, forms, terms, and specifications in the Bidding Document. Failure to furnish all information or authentic documentation required by the Bidding Document may result in rejection of the Bid.
2. The Bid shall comprise of two envelopes (one containing the Technical Bid and the other the Financial or Price Bid) to be submitted simultaneously under one main envelope.
3. The Bidder shall submit the Technical Bid and Financial Bid using the appropriate Bid Submission Format provided in Bidding/ Tender document or as requested in Bid document. The forms/ formats must be completed without any alterations to their format, and no substitutes shall be accepted.
4. Tender bid can be sent by post/ courier or submitted by hand at our office by time as specified in tender notice. Tenders received late will be rejected.
5. Bid can be submitted by hand or by post/ courier. For bids submitted by post or Courier, it is bidder's responsibility that bid reaches our office on or before the scheduled time and date.
6. In case tender opening date is declared a Holiday, bids shall be opened on next working day at the same time specified in tender.
7. The unit rates and the prices shall be quoted by the Bidder entirely in Indian Rupees unless otherwise specified in Bidding/ Tender document in case of International Competitive Bidding (ICB). All payments shall be made in Indian Rupees only, unless otherwise specified in the Bidding/ Tender document.
8. To establish their eligibility, Bidders shall complete the eligibility criteria specified /requested in the Bid/ Tender document.
9. To establish the conformity of the Goods and Related Services to the Bidding Document, the Bidder shall furnish as part of its Bid, the documentary evidence (specifications, designs and drawings and others), supply samples where asked for, demonstrate trials or carry out tests as specified in Bidding /tender document.
10. Any attempt by a Bidder to influence the Procuring Entity "The Jharkhand State Cooperative Milk Producers' Federation Ltd. (JMF)", in the examination, evaluation, comparison, and post qualification of the Bids or Contract award decisions may result in the rejection of its Bid, in addition to the legal action which may be taken by the Procuring Entity under the Act and the Rules.
11. Information relating to the examination, evaluation, comparison, and post-qualification of Bids, and recommendation of contract award, shall not be disclosed to Bidders or any other persons not officially concerned with such process until information on Contract award is communicated to all Bidders.
12. To assist in the examination, evaluation, comparison and qualification of the Technical or Financial Bids, the Bid evaluation committee may, at its discretion, ask any Bidder for a clarification regarding its Bid. The committee's request for clarification and the response of the Bidder shall be in writing.
13. Any clarification submitted by a Bidder with regard to his Bid that is not in response to a request by the Bid evaluation committee shall not be considered.
14. The determination of qualification of a Bidder in evaluation of Technical Bids shall be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder and in accordance with the qualification criteria indicated in Qualification and Evaluation Criteria. Factors not included in Qualification and Evaluation Criteria shall not be used in the evaluation of the Bidder's qualification.
15. The Bid evaluation committee shall have full powers to undertake negotiations where it deemed necessary. Negotiations may, however, be undertaken only with the lowest Bidder(s) only.
16. JMF reserves the right to accept or reject any Bid, and to annul the Bidding process and reject all Bids at any time prior to Contract award without assigning any reasons thereof and without thereby incurring any liability to the Bidders.
17. JMF shall award the contract to the Bidder whose offer has been determined to be the lowest in accordance with the evaluation criteria set out in Evaluation and Qualification Criteria and if the Bidder has been determined to be qualified to perform the contract satisfactorily.



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

### **3. ELIGIBILITY AND QUALIFICATION REQUIREMENTS**

The bidders must meet the following eligibility/ Qualifying criterias:

1. That, bidder in the same name & style, should be in same business at least for three years as on 30<sup>th</sup> December 2020 at the time of bid opening. In case of change of name of the bidder by merger /acquisitions/change in status, the bidder may be eligible based on the documentary evidence.
2. To justify the at least 3 years' experience (as above), the tenderer/ bidder must submit Job Completion Letters/ Certificates of having successfully completed similar works.
3. The tenderer/ bidder should have similar experience with Government Institutions, Semi Government and Dairy Cooperatives.
4. In case of Private Sectors/ Institutions, undertakings, should be any one of the following:
  - a. Three similar completed works costing not less than the amount equal to 40% of the offered Bidding Value/Cost.
  - OR
  - b. Two similar completed works costing not less than the amount equal to 50% of the offered Bidding Value/Cost.
  - OR
  - c. One similar completed work costing not less than the amount equal to 80% of the offered Bidding Value/Cost.
5. Statutory Audit Report of Last three (03) FY to be submitted along with Tender document in Technical Bid.
6. Average Annual Financial Turn-Over during the last 3 years, should be at least 80% of the offered Bidding Value/Cost.
7. Latest copy of GSTR-1 is required

**Note:**

1. All statutory requirement/compliance (Royalty, Labour Law, Mining Challan & Taxes) must be fulfilled by the bidder.
2. The contractor shall abide by the rules & regulations of Labour's Laws applicable in their case relating to weekly holidays, overtime allowance, leave with wages and compensatory holidays etc.
3. The contractor shall strictly implement all relevant provisions enumerated under Contract Labour (Regulation & Abolition) Act. 1970 and will submit all statutory documents and records as applicable to concerned authorities and shall take full responsibility for obtaining labour license from Central/State Authority as per the Act. He/she/they will also ensure timely submission of statutory returns as applicable in their case.
4. Similar work means construction of residential buildings and office buildings involving finishing items.
5. The determination of qualification of a Bidder in evaluation of Technical Bids shall be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder and in accordance with the qualification criteria indicated in Qualification and Evaluation Criteria. Factors not included in Qualification and Evaluation Criteria shall not be used in the evaluation of the Bidder's qualification.
6. JMF reserves its right to reject the tender on account of unsatisfactory past performance by the present tenderer in another project / sister unit awarded under different enquiry.
7. The tenderers are requested to visit the site before quoting for the work.





**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

#### **4. EARNEST MONEY DEPOSIT:**

- i. Technical Bid should accompany an Earnest Money Deposit of Rs. 26,000/- (Rupees Twenty-Six Thousand only) in the form of a Demand Draft drawn in favour of “**Jharkhand State Co-Op. Milk Producers’ Federation Ltd.**” payable at Ranchi on a scheduled/nationalized bank. JMF shall not be liable for payment of any interest on EMD.
  - a. Any request by the bidders to consider their EMD furnished by them to JMF for any other contract/ tender cannot be considered as EMD for this tender.
  - b. The EMD will be returned to the unsuccessful bidders soon after the orders are placed to the successful bidder. In case of successful bidder, the EMD shall be converted to performance security deposit and will be returned after completion of contract/ delivery, subject to successful performance.
  - c. If the tenders are cancelled or recalled on any ground(s), the EMD will be refunded to the agency/agencies.
  - d. The earnest money deposited for the tender will not be returned to the bidders till the acceptance of tender or three months or after finalization of tender, whichever is earlier.
- ii. The EMD will be forfeited in following cases:
  - a) If the bidder withdraws its tender before the finalization of tendering process/contract.
  - b) If the bidder fails to accept the order based on his offer (bid) and within the prescribed time.
  - c) If the performance during the contract period is found unsatisfactory
  - d) The Tender is liable to be rejected in case EMD at prescribed rate is not furnished along with the tender.



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**5. SCOPE OF WORK: -**

1. The scope of work includes all required activities for proper completion of work titled as “**CIVIL CONSTRUCTION OF PRODUCT PACKING ROOM & COLD STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT, HOTWAR**” as directed by the Engineer-in-Charge in accordance to the BOQ & Standard Technical Specification of this tender.
2. The bidders, at their own responsibility/cost/risk, are advised to visit and examine the site of works and obtain all information that may be necessary for preparing the bid and entering into a contract for execution of the works. It shall be deemed that the bidder has visited the site/ area and got fully acquainted with the working conditions/ other prevalent conditions/ fluctuations and has taken all the factors into account while bidding.
3. The work under proposal is to be completed in all respects for the successful completion and handing over the completed works to owner. All safety precautions are required to be taken during the construction period. On award of work, the contractor will carry out the Total stations survey and initial site levels, wherever necessary, as directed by Engineer-in- Charge.
4. The contractor shall employ labour in sufficient numbers either directly or through subcontractors to maintain the required date of progress and of quality to ensure workmanship to the degree specified in the contract and to the satisfaction of the Engineer – in – charge. The contractor shall not employ, in connection with the works, any person who has not completed eighteen years of age.
5. The above prices are inclusive of all costs towards tools, tackles, material, consumables, as well as sufficient number of skilled/ unskilled manpower, which shall be required for ensuring smooth execution of the work.
6. The Contractor shall pay to labour employed by him, either directly or through subcontractors, wages not less than fair wages, as defined in the Contractor’s Labour Regulations.
7. The Contractor shall in respect of labour employed by him, either directly or through subcontractors, comply with or cause to be complied with contractor’s labour Regulations in regard to all matters provided therein.
8. The Contractor shall comply with the provisions of the payment of Wages Act, 1936, Minimum Wages Act, 1948, Workmen’s Compensation Act 1923, Industrial Disputes Act, 1947, Maternity Benefit Act 1961, or any modifications thereof or any other law relating thereto and rules made there under from time to time.
9. The Engineer-in-charge shall deduct such amount from bills or security deposit of the Contractor and credit the same to the welfare fund constituted under Regulations. The decisions of the Engineer-in-charge in this respect shall be final and binding.
10. The contractor shall take all necessary safety precautions and arrange for appropriate appliances as per direction of JMF, or its authorized officials, to prevent loss to human lives, injuries to personnel engaged, and damage to property and environment.
11. All tools, tackles, lifting appliances, material handling equipment, scaffolds, cradles, safety nets, ladders, equipment etc. used by the contractor shall be of safe design and construction. These shall be tested and certificate of fitness obtained, before putting them to use and from time to time as instructed by authorized JMF official who shall have the right to ban the use of any item.



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

12. All the electrical equipment, connections and wiring for constructions, power, its Distribution and use shall conform to the requirement of Indian Electricity Act and Rules. Only electricians licensed by the appropriate statutory authority shall be employed by the contractor to carry out the all types of electrical works. All electrical appliances including portable electric tools used by the contractor shall have safe plugging system to source of power and be appropriately earthed.
13. The contractor shall arrange at his cost (wherever not specified), appropriate illumination at all work spots for safe working when natural daylight may not be adequate for clear visibility.
14. In case of any damage to property due to lapses by the contractor, JMF shall have the right to recover cost of such damages from payments due to the contractor after holding an appropriate enquiry.
15. In case of any delay in the completion of a job due to mishaps attributable to lapses by the contractor, JMF shall have the right to recover cost of such delay from payments due to the contractor, after notifying the contractor suitably and giving him opportunity to present his case.

## **6. GENERAL TERMS AND CONDITIONS:**

1. Tenderer should submit their valuable quotation in a sealed envelope super-scribing “**OFFER FOR CONSTRUCTION OF PRODUCT PACKING ROOM & COLD STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT, HOTWAR**” on or before **28 Jan 2021 by 05:00 pm** in the following address: Medha Dairy Plant, Hotwar, (A unit of Jharkhand Milk Federation), Beside Birsa Munda Central Jail, Hotwar, Ranchi, Jharkhand – 835217.
2. The Prices shall be quoted in Indian Rupees only.
3. Parties need to quote on the prescribed proforma, as attached.
  - a) The Bidder interested, shall fill their complete profile in the attached Vendor Registration Form.
  - b) The detailed Technical Specification is enclosed as Annexure – A.
  - c) The Supplier should quote for the job/ items in the prescribed format mention enclosed as Annex-B.
  - d) The detailed BOQ/SOQ of CONSTRUCTION OF PRODUCT PACKING ROOM & COLD STORAGE PLATFORM WORK AT MEDHA DAIRY PLANT, HOTWAR is enclosed as Annexure-C.
4. Payment Terms:
  - ii. 95% payment against Submission of Invoice/Bill duly certified by Plant & Project Head, JMF.
  - iii. Remaining 5% retention amount will be retained as security deposit and same will be released after 12 months from the date of completion of job.
5. Security Deposits @5% of the gross amount shall be deducted from each bill submitted by the contractor. The Security Deposit shall be refunded after successful completion of defect liability period.
6. The Time allowed for completion of the work is 90 days and the date of commencement shall be reckoned from the 7th day of issue of award letter.
7. Before tendering, the tenderer shall inspect the site to get fully acquainted about the site in regard to accessibility of site, nature and extent of ground working condition of site, its locality including stacking of materials, installations of tools and plants (T&P) etc., conditions affecting accommodations and movement of labour etc. for the satisfactory execution of the work contract. No claim whatsoever on such account shall be entertained by Jharkhand State Coop Milk Producers' Federation Ltd in any circumstances.
8. No material will be issued by the JMF department. Contractor has to arrange & provide all the materials and T&P etc. at his own cost at site.



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

9. Any damage done by the Contractor to the existing structure fittings/fixtures shall have to be made good by the contractor, at his own cost. In failure to do the same, the necessary cost for making the good shall be recovered from the final bill of the contractor.
10. Quantities mentioned in the schedule of work may decrease or increase as per the site conditions. Nothing shall be payable for any reduction in scope of work.
11. Quantities shown in the attached schedule are only tentative and approximate and are liable for variation without entitling the contractors to any compensation, provided the total value of the contract does not vary by more than 20% (twenty percent).
12. Samples of all the materials required to execute the work shall be approved brand & manufacture and are of best quality. The same shall have to be got approved by the contractor from the JMF Engineer-in-charge before execution of the work.
13. Tender submitted shall remain valid for 90 days from the date of opening for the purpose of acceptance and award of work, validity beyond 90 days from the date of opening shall be by mutual consent.
14. The tenderer shall quote rates both in figures and words. He shall also workout the amount for each item of work and writes in both figures and words. On check if there are differences between the rates quoted by the tenderer in words and in figures or in the amount worked out by him, the following procedure shall be followed:
  - i. When there is a difference between the rates in figures and in words, the rates which correspond to the amounts worked out by the tenderer shall be taken as correct.
  - ii. When the amount of an item is not worked out by the tenderer or it does not correspond with the rate written either in figures or in words, the rate quoted by the tenderer in words shall be taken as correct.
  - iii. When the rate quoted by the tenderer in figures and in words tallies but the amount is not worked out correctly the rate quoted by the tenderer shall be taken as correct and not the amount.
15. Except writing rates and amount, the tenderer should not write any conditions or make any changes, additions, alterations and modifications in the printed form of tenders. Tenderers who are desirous to offer rebate the same should be brought out separately in the covering letter and submitted along with the tender.
16. If the work by the contractor is delayed beyond the stipulated date of completion, Penalty shall be imposed @ 0.5% of the value of the work awarded for each week of delay, subject to a maximum of 10% of the gross amount of work done.
17. The Defect Liability Period shall be of 12 months and shall be start from the actual date of satisfactory completion of the work. Defects pointed out during defect liability period shall be made good by the contractor at his own cost; failure to do the same, the necessary cost for making the good shall be recovered from the amount of security deposit.
18. The Contractor should confirm any ambiguity and discrepancy related to the work and tender in writing before submitting the tender document.
19. Contractor has to ensure all the safety precautions related to its staff and labour, and also to ensure safety of all fittings of the adjoining complex at site during work execution at its own risk and cost.
20. JMF Reserves the right to reject all or to any of the tenders or to accept the tender or to accept the quotation/ tender either in full or in part or to split of the contract without assigning any reason.



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**21. VENDOR REGISTRATION FORM**

| No                                | Details  |                            |            |
|-----------------------------------|--|----------------------------|------------|
| 1                                 | Name of Vendor/ Bidder   |                            |            |
| 2                                 | Address Of Registered Office   |                            |            |
| 3                                 | Address Of Factory/ Works  |                            |            |
| 4                                 | Name Of Contact Person   |                            |            |
| 5                                 | Contact Nos.   |                            |            |
| 6                                 | Email Id   |                            |            |
| 7                                 | Type Of Firm : Ltd Co/ Pvt. Ltd. / Partnership/ Proprietor   |                            |            |
| 8                                 | Nature Of Firm: Manufacturer/ Traders / Autho. Dist. / Dealer  |                            |            |
| 9                                 | Year Of Establishment  |                            |            |
| 10                                | Name Of Product, you Deal  |                            |            |
|                                   | Please, Specify in separate sheet (As per below Format)  |                            |            |
|                                   | S. No  | Item Description (Shortly) | Make/Brand |
|                                   |  |                            |            |
| 11                                | G.S.T. No & Reg. Date  |                            |            |
| 12                                | PAN No & Date  |                            |            |
| 13                                | Turn Over Of last 3 Year (Rs.)   |                            |            |
|                                   | 1.   | 2.                         | 3.         |
| 14                                | If You have maintained any quality standard (Pl. Specify)  |                            |            |
| 15                                | Name Of Clients (If required, Pl. Specify in separate sheet)   |                            |            |
|                                   | 1.   | 2.                         | 3.         |
| 16                                | Min. Lead Time Required (Days)   |                            |            |
| 17                                | Bank Details   |                            |            |
|                                   | Name of Bank :<br>Branch Address:<br>Account No. :<br>IFSC Code :  |                            |            |
| 18                                | Documents to Be Attached   |                            |            |
|                                   | 1. Copy of Registration + PAN Copy + GST Regn.<br>2. ISO Certificates<br>3. Autho. Dealership<br>4. Fin. Statements<br>5. Product Brochures<br>6. Copy of PO's (Min.5) |                            |            |
| Recommendation:                   |  |                            |            |
| <b>Seal &amp; Sign. Of Vendor</b> |  |                            |            |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

ANNEXURE – A

**22. PERFORMA OF TECHNICAL BID**

Name of Agency: .....

Name of the authorized person who signed the tender documents: .....

Address of the Agency: .....

Ph No. / Mobile No. ....

E-mail ID: .....

**The tenderer needs to submit the following documents with their tender documents:**

The Bidder should furnish the details requested for in the format given below:

| Sl. No | Description of requirement   | Proof: Attached / Not Attached | Page Nos. |
|--------|--|--------------------------------|-----------|
| 1      | Certificate of the firm registered with Government of Jharkhand  |                                |           |
| 2      | Copy of terms and conditions and every page of the tender document duly signed with seal of the firm, in token of acceptance                           |                                |           |
| 3      | Earnest Money deposit of Rs. 26,000/- (Twenty-six Thousand Only)   |                                |           |
| 4      | COPY of PAN (PAN No.....)  |                                |           |
| 5      | COPY of GST Registration (GST No. ....)  |                                |           |
| 6      | Experience of at least three years in providing Civil Construction Works (Experience certificate/work orders)  |                                |           |
| 7      | Undertaking of the agency certifying that M/s.....have not been debarred from any department of State/ Central Govt. or PSU or any other Organization. |                                |           |
| 8      | Copies of Balance Sheet and P & L A/c for the last 3 years duly certified by CA  |                                |           |
| 9      | Financial/Price Bid Proforma completed & sealed in separate envelope   |                                |           |

**Note: All the documents must be self-attested.**

Seal of the Company/Firm:



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**ANNEXURE-B**

**23. PERFORMA OF FINANCIAL BID**

| <b>Product Packing &amp; Cold Storage Platform Construction at Medha Dairy Plant, Hotwar</b> |  |      |     |                         |      |      |               |      |        |  |
|--|--|------|-----|-------------------------|------|------|---------------|------|--------|--|
|  | Description of work                                      | Unit | NOS | L                       | B    | H    | QTY.          | RATE | AMOUNT |  |
|  | <b>EARTHWORK</b>   |      |     |                         |      |      |               |      |        |  |
| <b>1.01</b>  | <b>EXCAVATION</b>  |      |     |                         |      |      |               |      |        |  |
|  | FOR FOOTING ALL  | CUM. | 24  | 1.20                    | 1.20 | 1.20 | 41.47         |      |        |  |
|  | FOR BRICK WORK ALL                                       | CUM. | 1   | 107.20                  | 0.30 | 0.50 | 16.08         |      |        |  |
|  |  |      |     | <b>TOTAL</b>            |      |      | <b>57.55</b>  |      |        |  |
| <b>1.08</b>  | <b>P&amp;L STONE DUST FILLING</b>                        |      |     |                         |      |      |               |      |        |  |
|  | STONE DUST FILLING UNDER FLOOR                           | CUM. | 1   | 10.30                   | 5.80 | 0.95 | 56.75         |      |        |  |
|  | DO, UNDER COLD STORE FLOOR                               | CUM. | 1   | 10.50                   | 6.30 | 0.80 | 52.92         |      |        |  |
|  |  |      |     | <b>TOTAL</b>            |      |      | <b>109.67</b> |      |        |  |
|  |  |      |     | <b>EARTH WORK TOTAL</b> |      |      |               |      |        |  |
|  | <b>CONCRETE WORK</b>                                     |      |     |                         |      |      |               |      |        |  |
| <b>2.03</b>  | <b>P&amp;L M/C MIX PCC 1:4:8 (100 THK)</b>               |      |     |                         |      |      |               |      |        |  |
|  | FOR FOOTING ALL  | CUM. | 24  | 1.20                    | 1.20 | 0.10 | 3.46          |      |        |  |
|  | FOR BRICK WORK ALL                                       | CUM. | 1   | 107.20                  | 0.25 | 0.10 | 2.68          |      |        |  |
|  | UNDER PRODUCT PACKING FLOOR                              | CUM. | 1   | 10.30                   | 5.80 | 0.10 | 5.97          |      |        |  |
|  | UNDER COLD STORE FLOOR                                   | CUM. | 1   | 10.50                   | 6.30 | 0.10 | 6.62          |      |        |  |
|  |  |      |     | <b>TOTAL</b>            |      |      | <b>18.73</b>  |      |        |  |
| <b>2.06</b>  | <b>P&amp;L M/C MIX RCC M-25 (1:1:2) UP TO HPL</b>        |      |     |                         |      |      |               |      |        |  |
|  | RCC FOOTING  | CUM. | 24  | 1.00                    | 1.00 | 0.35 | 8.40          |      |        |  |
|  | RCC COLUMN   | CUM. | 24  | 0.25                    | 0.25 | 0.90 | 1.35          |      |        |  |
|  | RCC FLOOR BEAM   | CUM. | 1   | 107.20                  | 0.25 | 0.25 | 6.70          |      |        |  |
|  | 150MM RCC FLOORING COLD STORE                            | CUM. | 1   | 9.3                     | 6.3  | 0.15 | 8.79          |      |        |  |
|  | 100MM RCC DADO ALL SIDE COLD STORE                       | CUM. | 1   | 30.00                   | 0.45 | 0.10 | 1.35          |      |        |  |
|  | 150MM RCC FLOORING PROCESSING/PACKING                    | CUM. | 1   | 10.30                   | 7.00 | 0.15 | 10.82         |      |        |  |
|  |  |      |     | <b>TOTAL</b>            |      |      | <b>37.40</b>  |      |        |  |
| <b>2.06A</b>   | <b>P&amp;L M/C MIX RCC M-25 (1:1:2) PL TO ALL HEIGHT</b> |      |     |                         |      |      |               |      |        |  |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|             |  |      |     |              |      |       |               |  |  |
|-------------|--|------|-----|--------------|------|-------|---------------|--|--|
|             | RCC COLUMN   | CUM. | 11  | 0.25         | 0.25 | 3.25  | 2.23          |  |  |
|             | LINTEL   | CUM. | 1   | 43.80        | 0.25 | 0.15  | 1.64          |  |  |
|             | SLAB BEAM  | CUM. | 1   | 51.8         | 0.25 | 0.25  | 3.24          |  |  |
|             | SLAB   | CUM. | 1   | 10.30        | 5.80 | 0.125 | 7.47          |  |  |
|             | PARAPET COLUMN   | CUM. | 11  | 0.25         | 0.25 | 1.20  | 0.83          |  |  |
|             | COPING   | CUM. | 1   | 32.00        | 0.25 | 0.08  | 0.60          |  |  |
|             |  |      |     | <b>TOTAL</b> |      |       | <b>16.01</b>  |  |  |
| <b>2.09</b> | <b>P&amp;E SHUTTERING UP TO HIGHEST PLINTH LEVEL</b>           |      |     |              |      |       |               |  |  |
|             | FOOTING  | SQM  | 96  | 1.00         | 1    | 0.35  | 33.60         |  |  |
|             | RCC COLUMN   | SQM  | 96  | 0.25         | 1    | 0.9   | 21.60         |  |  |
|             | RCC FLOOR BEAM   | SQM  | 2   | 107.20       | 1    | 0.25  | 53.60         |  |  |
|             | RCC FLOOR COLD STORE   | SQM  | 1   | 31.2         | 1    | 0.15  | 4.68          |  |  |
|             | RCC DADO ALL SIDE  | SQM  | 1   | 30.00        | 1    | 0.45  | 13.50         |  |  |
|             | RCC FLOOR PROCESSING & PACKING                                 | SQM  | 1   | 34.60        | 1    | 0.15  | 5.19          |  |  |
|             |  |      |     | <b>TOTAL</b> |      |       | <b>132.17</b> |  |  |
| <b>2.10</b> | <b>P&amp;E SHUTTERING HPL TO ALL HEIGHT</b>                    |      |     |              |      |       |               |  |  |
|             | RCC COLUMN   | SQM  | 44  | 0.25         | 1    | 5.00  | 55.00         |  |  |
|             | LINTEL   | SQM  | 2   | 43.80        | 1    | 0.15  | 13.14         |  |  |
|             | SLAB BEAM  | SQM  | 2   | 51.8         | 1    | 0.25  | 25.90         |  |  |
|             | SLAB   | SQM  | 1   | 10.30        | 5.80 | 1     | 59.74         |  |  |
|             | DO, OUTER  | SQM  | 1   | 32.20        | 1    | 0.125 | 4.03          |  |  |
|             | PARAPET COLUMN   | SQM  | 44  | 0.25         | 1    | 1.20  | 13.20         |  |  |
|             | COPING   | SQM  | 2   | 32.00        | 1    | 0.075 | 4.80          |  |  |
|             |  |      |     | <b>TOTAL</b> |      |       | <b>175.81</b> |  |  |
| <b>2.16</b> | <b>PROVIDING, BENDING &amp; FIXING REINFORCEMENT/TMT STEEL</b> |      |     |              |      |       |               |  |  |
|             | FOOTING 10MM   | KG   | 384 | 1.20         | 1.00 | 0.62  | 284.31        |  |  |
|             | COLUMN C-1 12MM  | KG   | 64  | 7.50         | 1.00 | 0.89  | 426.24        |  |  |
|             | STIRUPPS COLUMN C-1 8MM  | KG   | 784 | 0.92         | 1.00 | 0.40  | 284.91        |  |  |
|             | COLUMN C-2 16MM  | KG   | 32  | 7.50         | 1.00 | 1.58  | 379.20        |  |  |
|             | STIRUPPS COLUMN C-2 8MM  | KG   | 392 | 0.92         | 1.00 | 0.40  | 142.45        |  |  |
|             | PLINTH BEAM 12MM   | KG   | 4   | 115.00       | 1.00 | 0.89  | 408.48        |  |  |





**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|             |   |      |     |       |      |      |                             |               |  |
|-------------|---|------|-----|-------|------|------|-----------------------------|---------------|--|
|             | STIRUPPS PLINTH BEAM 8MM  | KG   | 720 | 0.92  | 1.00 | 0.40 | 261.65                      |               |  |
|             | LINTEL BEAM 12 MM   | KG   | 4   | 50.00 | 1.00 | 0.89 | 177.60                      |               |  |
|             | STIRUPPS LINTEL BEAM 8MM  | KG   | 287 | 0.72  | 1.00 | 0.40 | 81.53                       |               |  |
|             | FLOOR PROCESSING & PACKING 8MM LONG   | KG   | 39  | 11    | 1    | 0.40 | 169.31                      |               |  |
|             | DO, SHORT 8MM   | KG   | 71  | 5.8   | 1    | 0.40 | 162.58                      |               |  |
|             | FLOOR COLD STORE 8MM LONG   | KG   | 42  | 9.3   | 1.00 | 0.40 | 154.29                      |               |  |
|             | DO, SHORT 8MM   | KG   | 62  | 6.3   | 1.00 | 0.40 | 154.29                      |               |  |
|             | RCC DADO COLD STORE 8MM LONG  | KG   | 4   | 10.7  | 1.00 | 0.40 | 16.91                       |               |  |
|             | DO, SHORT 8MM   | KG   | 208 | 0.45  | 1.00 | 0.40 | 36.97                       |               |  |
|             | SLAB BEAM 12 MM   | KG   | 4   | 50.00 | 1.00 | 0.89 | 177.60                      |               |  |
|             | STIRUPPS SLAB BEAM 8MM  | KG   | 287 | 0.92  | 1.00 | 0.40 | 104.17                      |               |  |
|             | SLAB 10MM @150C/C   | KG   | 69  | 5.8   | 1.00 | 0.62 | 300.73                      |               |  |
|             | SLAB 8MM @150C/C  | KG   | 39  | 10.3  | 1.00 | 0.40 | 220.32                      |               |  |
|             |   |      |     |       |      |      | <b>TOTAL</b>                | <b>3943.5</b> |  |
|             |   |      |     |       |      |      | <b>CONCRETE WORK TOTAL</b>  |               |  |
|             | <b>BRICK WORK</b>   |      |     |       |      |      |                             |               |  |
| <b>3.01</b> | <b>250MM BRICK WORK 1:6 UP TO HIGHEST PLINTH LEVEL</b>                        |      |     |       |      |      |                             |               |  |
|             | BELOW PLINTH BEAM PACKING & PROESSING   | CUM. | 1   | 58.90 | 0.25 | 1.20 | 17.67                       |               |  |
|             | DO, COLD STORAGE AREA   | CUM. | 1   | 46.80 | 0.25 | 0.85 | 9.95                        |               |  |
|             |   |      |     |       |      |      | <b>TOTAL</b>                | <b>27.62</b>  |  |
| <b>3.02</b> | <b>250MM BRICK WORK 1:6 UP TO ALL HEIGHT</b>                                  |      |     |       |      |      |                             |               |  |
|             | PACKING & PROCESSING AREA LONG WALL   | CUM. | 2   | 10.30 | 0.25 | 5.00 | 25.75                       |               |  |
|             | DO, SHORT WALL  | CUM. | 3   | 4.80  | 0.25 | 5.00 | 18.00                       |               |  |
|             |   |      |     |       |      |      | <b>TOTAL</b>                | <b>43.75</b>  |  |
|             |   |      |     |       |      |      | <b>BRICK WORK TOTAL</b>     |               |  |
|             | <b>ALUMINIUM WORK</b>   |      |     |       |      |      |                             |               |  |
| <b>4.01</b> | <b>1.5MM THICK POWDER COATED ALUMINIUM DOOR PARTLY GLAZED PARTLY PANELLED</b> | SQM. | 4   | 1.00  | 1.00 | 2.10 | 8.40                        |               |  |
|             |   |      |     |       |      |      | <b>ALUMINIUM WORK TOTAL</b> |               |  |
|             | <b>FINISHING WORK</b>   |      |     |       |      |      |                             |               |  |
| <b>5.01</b> | <b>P&amp;A 12MM THICK PLASTER TO ALL HEIGHT (1:4)</b>                         |      |     |       |      |      |                             |               |  |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|             |   |      |   |                             |              |          |               |  |  |  |
|-------------|---|------|---|-----------------------------|--------------|----------|---------------|--|--|--|
|             | PACKING & PROCESSING AREA LONG WALL                                   | SQM. | 2 | 10.30                       | 1            | 5.00     | 103.00        |  |  |  |
|             | DO, SHORT WALL  | SQM. | 6 | 4.80                        | 1            | 5.00     | 144.00        |  |  |  |
|             | DO, SLAB BOTTOM   | SQM. | 1 | 10.30                       | 1            | 5.80     | 59.74         |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>306.74</b> |  |  |  |
| <b>5.03</b> | <b>P&amp;A 19MM THICK SAND FACED PLASTER ON OUTER SURFACE OF WALL</b> |      |   |                             |              |          |               |  |  |  |
|             | COLD STORAGE AREA   | SQM. | 1 | 57.86                       | 1            | 0.45     | 26.04         |  |  |  |
|             | OUTER WALL PACKING & PROCESSING AREA                                  | SQM. | 1 | 26.40                       | 1            | 5        | 132.00        |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>158.04</b> |  |  |  |
| <b>5.09</b> | <b>P&amp;A PLASTIC EMULSION PAINT</b>                                 |      |   |                             |              |          |               |  |  |  |
|             | AS PER PLASTER QUANTITY   | SQM. |   |                             |              |          | 306.74        |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>306.74</b> |  |  |  |
| <b>5.14</b> | <b>P&amp;A APEX ULTIMA PAINT ON OUTER WALL</b>                        |      |   |                             |              |          |               |  |  |  |
|             | AS PER PLASTER QUANTITY   | SQM. |   |                             |              |          | 158.04        |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>158.04</b> |  |  |  |
|             |   |      |   | <b>FINISHING WORK TOTAL</b> |              |          |               |  |  |  |
|             | <b>FLOORING</b>   |      |   |                             |              |          |               |  |  |  |
| <b>6.05</b> | <b>P&amp;L PRE-POLISHED M/C CUT KOTA STONE OF 20-25MM THICK</b>       |      |   |                             |              |          |               |  |  |  |
|             | PACKING & PROCESSING AREA   | SQM. | 1 | <b>5.80</b>                 | <b>11.00</b> | <b>1</b> | 63.80         |  |  |  |
|             | COLD STORAGE AREA   | SQM. | 1 | <b>9.30</b>                 | <b>6.30</b>  | <b>1</b> | 58.59         |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>63.80</b>  |  |  |  |
| <b>6.20</b> | <b>P&amp;L CERAMIC TILES IN DADO/WALL UP TO 1.5M</b>                  |      |   |                             |              |          |               |  |  |  |
|             | STORAGE ROOM  | SQM. | 1 | 17.60                       | 1            | 1.50     | 26.40         |  |  |  |
|             | PACKING ROOM  | SQM. | 1 | 21.60                       | 1            | 1.50     | 32.40         |  |  |  |
|             | PROCESSING ROOM   | SQM. | 1 | 21.60                       | 1            | 1.5      | 32.40         |  |  |  |
|             |   |      |   | <b>TOTAL</b>                |              |          | <b>91.20</b>  |  |  |  |
|             |   |      |   | <b>FLOORING WORK TOTAL</b>  |              |          |               |  |  |  |
|             | <b>MISCELLANEOUS WORK</b>   |      |   |                             |              |          |               |  |  |  |
| <b>9.04</b> | <b>P&amp;F HEAVY DUTY HYDRAULIC DOOR CLOSER</b>                       | NOS  | 4 | 1                           | 1            | 1        | 4.00          |  |  |  |
| <b>9.06</b> | <b>P&amp;F JHARIS 150 TO 250MM WIDE</b>                               | RM   | 1 | 20                          | 1            | 1        | 20.00         |  |  |  |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|   |  |      |                                   |     |     |     |        |  |  |                    |  |
|---|--|------|-----------------------------------|-----|-----|-----|--------|--|--|--------------------|--|
| 9.07  | DISMANTLING BRICK WORK   | CUM. | 1                                 | 1   | 1   | 2.1 | 2.10   |  |  |                    |  |
| 9.08  | DISMANTLING RCC WORK   | CUM. | 1                                 | 9.4 | 9.4 | 0.3 | 26.51  |  |  |                    |  |
| 9.21  | DISMANTLING TILE IN WALL/FLOOR/ SKIRTING                       | SQM. | 2                                 | 1.2 | 1   | 2.1 | 5.04   |  |  |                    |  |
| 12.10   | P&F 150MM UPVC NB RAIN WATER PIPE                              | RM   | 2                                 | 1   | 1   | 5   | 10.00  |  |  |                    |  |
|   |  |      | <b>MISCELLANEOUS WORK TOTAL</b>   |     |     |     |        |  |  |                    |  |
| <b>ELECTRICAL WORKS</b>   |  |      |                                   |     |     |     |        |  |  |                    |  |
| 11.01   | P&F ZINC CHROMATE PASSIVATED MS BOX WITH MOULDED SHEET COVER   | No.  | 3                                 | 1   | 1   | 1   | 3.00   |  |  |                    |  |
| 11.03   | P&F HEAVY DUTY CONDUIT FOR LIGHT & FAN POINT                   | No.  | 1                                 | 50  | 1   | 1   | 50.00  |  |  |                    |  |
| 11.05   | P&F HEAVY DUTY 300MM DIA EXHAUST FAN WITHOUT REGULATOR         | NO.  | 3                                 | 1   | 1   | 1   | 3.00   |  |  |                    |  |
| 11.07   | P&F Heavy DUTY 2x4 SQM WIRES FOR LIGHT/FAN POINTS              | RM   | 1                                 | 150 | 1   | 1   | 150.00 |  |  |                    |  |
| 11.08   | P&F TUBE LIGHT OF 40W FOR LIGHT POINT INCLUDING ALL ACESSORIES | NOS  | 7                                 | 1   | 1   | 1   | 7.00   |  |  |                    |  |
|   |  |      | <b>TOTAL AMOUNT OF FINAL BILL</b> |     |     |     |        |  |  |                    |  |
|   |  |      |                                   |     |     |     |        |  |  | GST @12 %          |  |
|   |  |      |                                   |     |     |     |        |  |  | <b>GRAND TOTAL</b> |  |
| <b>NOTE:</b>  |  |      |                                   |     |     |     |        |  |  |                    |  |
| 1. All the work will be carried out as per latest relevant IS code specifications of civil engineering & standard civil tender document technical specifications of JMF. In case of any query feel free to contact JMF for clarifications prior to quote. |  |      |                                   |     |     |     |        |  |  |                    |  |
| 2. Approved Make: Cement: Ultratech/ACC/Birla Gold/ Lafarge TMT Fe:500D: TATA/SAIL/JINDAL   |  |      |                                   |     |     |     |        |  |  |                    |  |
| 3. All the materials which is supposed to use in project needs to be approved by JMF E/I.   |  |      |                                   |     |     |     |        |  |  |                    |  |

This is to certify that I/We before signing this tender have read and fully understood all the terms and conditions contained herein and undertake myself/ourselves to abide by them.

**Note: Goods and Service Tax (GST) as per prevalent rules shall be paid by PURCHASER”, if applicable**

**Date:** \_\_\_\_\_ **(Signature of Bidder with seal)**  
**Name:** \_\_\_\_\_  
**Seal:** \_\_\_\_\_



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**ANNEXURE-C**

**24. DETAILED BOQ/SOQ FOR PRODUCT PACKING & COLD STORAGE  
PLATFORM CONSTRUCTION AT MEDHA DAIRY PLANT HOTWAR**

|                      | Description of work                                      | Unit | NOS | L            | B    | H     | QTY.          |
|----------------------|--|------|-----|--------------|------|-------|---------------|
| <b>EARTHWORK</b>     |  |      |     |              |      |       |               |
| <b>1.01</b>          | <b>EXCAVATION</b>  |      |     |              |      |       |               |
|                      | FOR FOOTING ALL  | CUM. | 24  | 1.20         | 1.20 | 1.20  | 41.47         |
|                      | FOR BRICK WORK ALL                                       | CUM. | 1   | 107.20       | 0.30 | 0.50  | 16.08         |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>57.55</b>  |
| <b>1.08</b>          | <b>P&amp;L STONE DUST FILLING</b>                        |      |     |              |      |       |               |
|                      | STONE DUST FILLING UNDER FLOOR                           | CUM. | 1   | 10.30        | 5.80 | 0.95  | 56.75         |
|                      | DO, UNDER COLD STORE FLOOR                               | CUM. | 1   | 10.50        | 6.30 | 0.80  | 52.92         |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>109.67</b> |
| <b>CONCRETE WORK</b> |  |      |     |              |      |       |               |
| <b>2.03</b>          | <b>P&amp;L M/C MIX PCC 1:4:8 (100 THK)</b>               |      |     |              |      |       |               |
|                      | FOR FOOTING ALL  | CUM. | 24  | 1.20         | 1.20 | 0.10  | 3.46          |
|                      | FOR BRICK WORK ALL                                       | CUM. | 1   | 107.20       | 0.25 | 0.10  | 2.68          |
|                      | UNDER PRODUCT PACKING FLOOR                              | CUM. | 1   | 10.30        | 5.80 | 0.10  | 5.97          |
|                      | UNDER COLD STORE FLOOR                                   | CUM. | 1   | 10.50        | 6.30 | 0.10  | 6.62          |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>18.73</b>  |
| <b>2.06</b>          | <b>P&amp;L M/C MIX RCC M-25 (1:1:2) UP TO HPL</b>        |      |     |              |      |       |               |
|                      | RCC FOOTING  | CUM. | 24  | 1.00         | 1.00 | 0.35  | 8.40          |
|                      | RCC COLUMN   | CUM. | 24  | 0.25         | 0.25 | 0.90  | 1.35          |
|                      | RCC FLOOR BEAM   | CUM. | 1   | 107.20       | 0.25 | 0.25  | 6.70          |
|                      | 150MM RCC FLOORING COLD STORE                            | CUM. | 1   | 9.3          | 6.3  | 0.15  | 8.79          |
|                      | 100MM RCC DADO ALL SIDE COLD STORE                       | CUM. | 1   | 30.00        | 0.45 | 0.10  | 1.35          |
|                      | 150MM RCC FLOORING PROCESSING/PACKING                    | CUM. | 1   | 10.30        | 7.00 | 0.15  | 10.82         |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>37.40</b>  |
| <b>2.06A</b>         | <b>P&amp;L M/C MIX RCC M-25 (1:1:2) PL TO ALL HEIGHT</b> |      |     |              |      |       |               |
|                      | RCC COLUMN   | CUM. | 11  | 0.25         | 0.25 | 3.25  | 2.23          |
|                      | LINTEL   | CUM. | 1   | 43.80        | 0.25 | 0.15  | 1.64          |
|                      | SLAB BEAM  | CUM. | 1   | 51.8         | 0.25 | 0.25  | 3.24          |
|                      | SLAB   | CUM. | 1   | 10.30        | 5.80 | 0.125 | 7.47          |
|                      | PARAPET COLUMN   | CUM. | 11  | 0.25         | 0.25 | 1.20  | 0.83          |
|                      | COPING   | CUM. | 1   | 32.00        | 0.25 | 0.08  | 0.60          |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>16.01</b>  |
| <b>2.09</b>          | <b>P&amp;E SHUTTERING UP TO HIGHEST PLINTH LEVEL</b>     |      |     |              |      |       |               |
|                      | FOOTING  | SQM  | 96  | 1.00         | 1    | 0.35  | 33.60         |
|                      | RCC COLUMN   | SQM  | 96  | 0.25         | 1    | 0.9   | 21.60         |
|                      | RCC FLOOR BEAM   | SQM  | 2   | 107.20       | 1    | 0.25  | 53.60         |
|                      | RCC FLOOR COLD STORE                                     | SQM  | 1   | 31.2         | 1    | 0.15  | 4.68          |
|                      | RCC DADO ALL SIDE  | SQM  | 1   | 30.00        | 1    | 0.45  | 13.50         |
|                      | RCC FLOOR PROCESSING & PACKING                           | SQM  | 1   | 34.60        | 1    | 0.15  | 5.19          |
|                      |  |      |     | <b>TOTAL</b> |      |       | <b>132.17</b> |
| <b>2.10</b>          | <b>P&amp;E SHUTTERING HPL TO ALL HEIGHT</b>              |      |     |              |      |       |               |
|                      | RCC COLUMN   | SQM  | 44  | 0.25         | 1    | 5.00  | 55.00         |
|                      | LINTEL   | SQM  | 2   | 43.80        | 1    | 0.15  | 13.14         |
|                      | SLAB BEAM  | SQM  | 2   | 51.8         | 1    | 0.25  | 25.90         |
|                      | SLAB   | SQM  | 1   | 10.30        | 5.80 | 1     | 59.74         |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|             |  |                             |     |              |      |       |               |
|-------------|--|-----------------------------|-----|--------------|------|-------|---------------|
|             | DO, OUTER  | SQM                         | 1   | 32.20        | 1    | 0.125 | 4.03          |
|             | PARAPET COLUMN   | SQM                         | 44  | 0.25         | 1    | 1.20  | 13.20         |
|             | COPING   | SQM                         | 2   | 32.00        | 1    | 0.075 | 4.80          |
|             |  |                             |     | <b>TOTAL</b> |      |       | <b>175.81</b> |
| <b>2.16</b> | <b>PROVIDING, BENDING &amp; FIXING REINFORCEMENT/TMT STEEL</b>               |                             |     |              |      |       |               |
|             | FOOTING 10MM   | KG                          | 384 | 1.20         | 1.00 | 0.62  | 284.31        |
|             | COLUMN C-1 12MM  | KG                          | 64  | 7.50         | 1.00 | 0.89  | 426.24        |
|             | STIRUPPS COLUMN C-1 8MM  | KG                          | 784 | 0.92         | 1.00 | 0.40  | 284.91        |
|             | COLUMN C-2 16MM  | KG                          | 32  | 7.50         | 1.00 | 1.58  | 379.20        |
|             | STIRUPPS COLUMN C-2 8MM  | KG                          | 392 | 0.92         | 1.00 | 0.40  | 142.45        |
|             | PLINTH BEAM 12MM   | KG                          | 4   | 115.00       | 1.00 | 0.89  | 408.48        |
|             | STIRUPPS PLINTH BEAM 8MM   | KG                          | 720 | 0.92         | 1.00 | 0.40  | 261.65        |
|             | LINTEL BEAM 12 MM  | KG                          | 4   | 50.00        | 1.00 | 0.89  | 177.60        |
|             | STIRUPPS LINTEL BEAM 8MM   | KG                          | 287 | 0.72         | 1.00 | 0.40  | 81.53         |
|             | FLOOR PROCESSING & PACKING 8MM<br>LONG                                       | KG                          | 39  | 11           | 1    | 0.40  | 169.31        |
|             | DO, SHORT 8MM  | KG                          | 71  | 5.8          | 1    | 0.40  | 162.58        |
|             | FLOOR COLD STORE 8MM LONG  | KG                          | 42  | 9.3          | 1.00 | 0.40  | 154.29        |
|             | DO, SHORT 8MM  | KG                          | 62  | 6.3          | 1.00 | 0.40  | 154.29        |
|             | RCC DADO COLD STORE 8MM LONG   | KG                          | 4   | 10.7         | 1.00 | 0.40  | 16.91         |
|             | DO, SHORT 8MM  | KG                          | 208 | 0.45         | 1.00 | 0.40  | 36.97         |
|             | SLAB BEAM 12 MM  | KG                          | 4   | 50.00        | 1.00 | 0.89  | 177.60        |
|             | STIRUPPS SLAB BEAM 8MM   | KG                          | 287 | 0.92         | 1.00 | 0.40  | 104.17        |
|             | SLAB 10MM @150C/C  | KG                          | 69  | 5.8          | 1.00 | 0.62  | 300.73        |
|             | SLAB 8MM @150C/C   | KG                          | 39  | 10.3         | 1.00 | 0.40  | 220.32        |
|             |  |                             |     | <b>TOTAL</b> |      |       | <b>3943.5</b> |
|             | <b>BRICK WORK</b>  |                             |     |              |      |       |               |
| <b>3.01</b> | <b>250MM BRICK WORK 1:6 UP TO HIGHEST<br/>PLINTH LEVEL</b>                   |                             |     |              |      |       |               |
|             | BELOW PLINTH BEAM PACKING &<br>PROESSING                                     | CUM.                        | 1   | 58.90        | 0.25 | 1.20  | 17.67         |
|             | DO, COLD STORAGE AREA  | CUM.                        | 1   | 46.80        | 0.25 | 0.85  | 9.95          |
|             |  |                             |     | <b>TOTAL</b> |      |       | <b>27.62</b>  |
| <b>3.02</b> | <b>250MM BRICK WORK 1:6 UP TO ALL HEIGHT</b>                                 |                             |     |              |      |       |               |
|             | PACKING & PROCESSING AREA LONG<br>WALL                                       | CUM.                        | 2   | 10.30        | 0.25 | 5.00  | 25.75         |
|             | DO, SHORT WALL   | CUM.                        | 3   | 4.80         | 0.25 | 5.00  | 18.00         |
|             |  |                             |     | <b>TOTAL</b> |      |       | <b>43.75</b>  |
|             | <b>ALUMINIUM WORK</b>  |                             |     |              |      |       |               |
| <b>4.01</b> | 1.5MM THICK POWDER COATED<br>ALUMINIUM DOOR PARTLY GLAZED<br>PARTLY PANELLED | SQM.                        | 4   | 1.00         | 1.00 | 2.10  | 8.40          |
|             |  | <b>ALUMINIUM WORK TOTAL</b> |     |              |      |       | <b>8.40</b>   |
|             | <b>FINISHING WORK</b>  |                             |     |              |      |       |               |
| <b>5.01</b> | <b>P&amp;A 12MM THICK PLASTER TO ALL HEIGHT (1:4)</b>                        |                             |     |              |      |       |               |
|             | PACKING & PROCESSING AREA LONG<br>WALL                                       | SQM.                        | 2   | 10.30        | 1    | 5.00  | 103.00        |
|             | DO, SHORT WALL   | SQM.                        | 6   | 4.80         | 1    | 5.00  | 144.00        |
|             | DO, SLAB BOTTOM  | SQM.                        | 1   | 10.30        | 1    | 5.80  | 59.74         |
|             |  |                             |     | <b>TOTAL</b> |      |       | <b>306.74</b> |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

|              |   |      |   |              |              |          |               |
|--------------|---|------|---|--------------|--------------|----------|---------------|
| <b>5.03</b>  | <b>P&amp;A 19MM THICK SAND FACED PLASTER ON OUTER SURFACE OF WALL</b> |      |   |              |              |          |               |
|              | COLD STORAGE AREA   | SQM. | 1 | 57.86        | 1            | 0.45     | 26.04         |
|              | OUTER WALL PACKING & PROCESSING AREA                                  | SQM. | 1 | 26.40        | 1            | 5        | 132.00        |
|              |   |      |   | <b>TOTAL</b> |              |          | <b>158.04</b> |
| <b>5.09</b>  | <b>P&amp;A PLASTIC EMULSION PAINT</b>                                 |      |   |              |              |          |               |
|              | AS PER PLASTER QUANTITY   | SQM. |   |              |              |          | 306.74        |
|              |   |      |   | <b>TOTAL</b> |              |          | <b>306.74</b> |
| <b>5.14</b>  | <b>P&amp;A APEX ULTIMA PAINT ON OUTER WALL</b>                        |      |   |              |              |          |               |
|              | AS PER PLASTER QUANTITY   | SQM. |   |              |              |          | 158.04        |
|              |   |      |   | <b>TOTAL</b> |              |          | <b>158.04</b> |
|              | <b>FLOORING</b>   |      |   |              |              |          |               |
| <b>6.05</b>  | <b>P&amp;L PRE-POLISHED M/C CUT KOTA STONE OF 20-25MM THICK</b>       |      |   |              |              |          |               |
|              | PACKING & PROCESSING AREA   | SQM. | 1 | <b>5.80</b>  | <b>11.00</b> | <b>1</b> | 63.80         |
|              | COLD STORAGE AREA   | SQM. | 1 | <b>9.30</b>  | <b>6.30</b>  | <b>1</b> | 58.59         |
|              |   |      |   | <b>TOTAL</b> |              |          | <b>63.80</b>  |
| <b>6.20</b>  | <b>P&amp;L CERAMIC TILES IN DADO/WALL UP TO 1.5M</b>                  |      |   |              |              |          |               |
|              | STORAGE ROOM  | SQM. | 1 | 17.60        | 1            | 1.50     | 26.40         |
|              | PACKING ROOM  | SQM. | 1 | 21.60        | 1            | 1.50     | 32.40         |
|              | PROCESSING ROOM   | SQM. | 1 | 21.60        | 1            | 1.5      | 32.40         |
|              |   |      |   | <b>TOTAL</b> |              |          | <b>91.20</b>  |
|              | <b>MISCELLANEOUS WORK</b>   |      |   |              |              |          |               |
| <b>9.04</b>  | <b>P&amp;F HEAVY DUTY HYDRAULIC DOOR CLOSER</b>                       | NOS  | 4 | 1            | 1            | 1        | 4.00          |
| <b>9.06</b>  | <b>P&amp;F JHARIS 150 TO 250MM WIDE</b>                               | RM   | 1 | 20           | 1            | 1        | 20.00         |
| <b>9.07</b>  | <b>DISMANTLING BRICK WORK</b>   | CUM. | 1 | 1            | 1            | 2.1      | 2.10          |
| <b>9.08</b>  | <b>DISMANTLING RCC WORK</b>   | CUM. | 1 | 9.4          | 9.4          | 0.3      | 26.51         |
| <b>9.21</b>  | <b>DISMANTLING TILE IN WALL/FLOOR/SKIRTING</b>                        | SQM. | 2 | 1.2          | 1            | 2.1      | 5.04          |
| <b>12.10</b> | <b>P&amp;F 150MM UPVC NB RAIN WATER PIPE</b>                          | RM   | 2 | 1            | 1            | 5        | 10.00         |
|              | <b>ELECTRICAL WORKS</b>   |      |   |              |              |          |               |
| 11.01        | P&F ZINC CHROMATE PASSIVATED MS BOX WITH MOULDED SHEET COVER          | No.  | 3 | 1            | 1            | 1        | 3.00          |
| 11.03        | P&F HEAVY DUTY CONDUIT FOR LIGHT & FAN POINT                          | No.  | 1 | 50           | 1            | 1        | 50.00         |
| 11.05        | P&F HEAVY DUTY 300MM DIA EXHAUST FAN WITHOUT REGULATOR                | NO.  | 3 | 1            | 1            | 1        | 3.00          |
| 11.07        | P&F Heavy DUTY 2x4 SQM WIRES FOR LIGHT/FAN POINTS                     | RM   | 1 | 150          | 1            | 1        | 150.00        |
| 11.08        | P&F TUBE LIGHT OF 40W FOR LIGHT POINT INCLUDING ALL ACCESSORIES       | NOS  | 7 | 1            | 1            | 1        | 7.00          |



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**UNDERTAKING & ACCEPTANCE LETTER BY THE CIVIL CONTRACTOR/AGENCY**

I/We have carefully gone through the various terms and conditions listed in the Tender Form (Technical & Financial Bid) for **Product Packing & Cold Storage Platform Construction at Medha Dairy Plant Hotwar** at Jharkhand State Cooperative Milk Producers' Federation Ltd ("PURCHASER"). I/We agree to all these conditions and offer to Product Packing & Cold Storage Platform Construction at Medha Dairy Plant Hotwar at "PURCHASER". I/We are making this offer after carefully reading the conditions and understanding the same without any kind of pressure or influence from any source whatsoever. I/We have inspected the Medha Dairy Plant (Hotwar Location) and have acquainted ourselves with the tasks required to be carried out, before making this offer. I/We hereby sign this undertaking in token of our acceptance of various conditions listed above.

Place: \_\_\_\_\_

Signature of Contractor/Agency

Date: \_\_\_\_\_

Address: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Mob: \_\_\_\_\_

Email ID: \_\_\_\_\_



**JHARKHAND STATE COOPERATIVE MILK PRODUCERS'  
FEDERATION LIMITED  
REQUEST FOR QUOTATION**

**CERTIFICATE OF NO DEVIATION**

I / We ..... of M/s ..... Hereby certify that there is no deviation from the tender conditions either technical or commercial and I am /We are agreeing to all the terms and conditions mentioned in the Tender Specification.

Date:

Signature of the tenderer